

Draft Drainage 2019/20 Capital Programme

Programme: Drainage				
Project Name/Location	Division	District	Project Description	Estimate
Countywide Capital Allocation:				£1,000,000
19/20 B6254 Kirkby Lonsdale Road, Arkholme	Lancaster Rural North	Lancaster	Upsize the culvert from 100mm to 150mm downhill from the Forge, Snab Green Lane	£25,000
19/20 Morecambe Road/school watercourses	Morecambe South & Skerton	Lancaster	Clean out dykes and survey of drain under Hadrians Road	£15,000
19/20 A6068 Padiham Barrowford bypass	Pendle Hill	Pendle	Upgrade drainage and culvert repairs	£28,000
19/20 Ash Lane brick culvert phase 2	Fylde East	Fylde	Construction of phase 2	£75,000
19/20 A59 Preston New Road, Samlesbury	South Ribble East	South Ribble	Upsize 7 carriageway gullies on hill above former police houses to catch volume of surface water and reduce ponding in front of residential property	£15,000
19/20 New Cut Lane, Halsall	West Lancashire West	West Lancs	Drainage investigation, and renew surface water drain in highway	£35,000
19/20 A588 Marsh Lane, Cockerham	Lancaster Central	Lancaster	Drainage carriageway and footway works to install non-return valves at private connections, and increase drainage pipe capacity	£50,000
19/20 C278 Chain Lane, Staining phase 1	Fylde West	Fylde	Repair and improve capacity of highway drainage system at roundabout, including repairs to damaged 3 rd party assets	£80,000
19/20 Hall Lane, Appley Bridge	Skelmersdale East	West Lancs	Rebuild culvert headwall	£20,000
19/20 Higher Lane, Dalton near Brookside	West Lancashire East	West Lancs	Replace culvert	£20,000
19/20 Asmall Lane, Halsall	West Lancashire West	West Lancs	Install 300m of new 300mm diameter pipe and manholes	£52,000

Programme: Drainage				
Project Name/Location	Division	District	Project Description	Estimate
19/20 Towneley Close, Lancaster City	Lancaster Central	Lancaster	Additional gullies and capacity to reduce risk of flooding	£50,000
19/20 Redgate, Ormskirk	Ormskirk	West Lancs	Replace culvert under the highway (from ginnel to back of No 36)	£30,000
19/20 Sandy Lane, Accrington Phase 2 - option appraisal	Accrington South	Hyndburn	Review options identified in phase 1	£10,000
19/20 Footpath 2 Barrow Lane/ Hexham Road, Torrisholme	Morecambe South	Lancaster	Install debris trap/s to allow for cleaning and reduce risks of gravel reaching highway drainage systems	£20,000
19/20 Hatlex Lane, Hest Bank	Morecambe North	Lancaster	Install gullies and carrier drain, with 5 pairs of gullies	£50,000
19/20 Edge End Avenue, Brierfield (rear of 21 - 27) Phase 2	Pendle Hill	Pendle	Complete works to locate culverted watercourse under footpath and back gardens. Repair any damage and clear outfall to highway drainage	£30,000
19/20 Red Cat Lane, Burscough	Burscough and Rufford	West Lancs	Install 140m of new 300mm diameter pipe and manholes	£30,000
19/20 Lancaster Road, Overton	Heysham	Lancaster	Continuing investigation into drainage system	£15,000
19/20 Brookhouse/Caton	Lancaster Rural East	Lancaster	Investigation of current highway system	£10,000
19/29 Priest Hutton highway drainage improvements	Lancaster Rural North	Lancaster	Highway drainage improvements	£15,000
19/20 A6 Hampson Road junction	Lancaster Rural East	Lancaster	Culvert damage assessment and options review	£10,000
19/20 A683 Denny Beck to Scarthwaite Bends	Lancaster Rural East	Lancaster	Clean system and check for faults	£6,000

Programme: Drainage				
Project Name/Location	Division	District	Project Description	Estimate
19/20 A6 Milnthorpe Road	Lancaster Rural North	Lancaster	De-silting of drainage system and pipe work repairs	£25,000
19/20 A6 Scotforth Road	Lancaster Central, Lancaster South East, Lancaster Rural East	Lancaster	De-silting of the carrier drain	£25,000
19/20 Abbeystead Lane Cattle grid to Abbeystead Road	Lancaster Rural East	Lancaster	Clean system and check for faults	£6,000
19/20 Burnley Road, Hapton	Padiham and Burnley West	Burnley	Drain survey and lay new drainage	£12,000
19/20 Carr Lane, Middleton	Heysham	Lancaster	Review drainage system	£15,000
19/20 Moor Lane Wray Curwen Hall Farm	Lancaster Rural East	Lancaster	Relay drain and check outfalls	£10,000
19/20 Crown Point Road between 385350 and Burnley Road	Burnley Rural	Burnley	Lay 145m of 150mm pipe, and 4 gullies	£36,000
19/20 Castle Lane, Ormskirk	West Lancashire East	West Lancs	Install 270m of new 225mm diameter pipe and manholes	£45,000
19/20 Sawley Old Brow Phase 2	Ribble Valley North East	Ribble Valley	Relocate private septic tank discharge to United Utilities foul sewer	£10,000
19/20 New Road Silverdale before Sand Pool	Lancaster Rural North	Lancaster	Culvert collapse repairs	£15,000
19/20 Ravensclose Road, Wennington Ravens Close Farm	Lancaster Rural East	Lancaster	Install new gullies and drain	£15,000

Programme: Drainage				
Project Name/Location	Division	District	Project Description	Estimate
19/20 Moor Lane Wray, Curwen Hall Farm	Lancaster Rural East	Lancaster	Relay drain and check outfalls	£10,000
19/20 C332 Pedders Lane junction with Whinfield Lane	Preston South West	Preston	Works in 2 locations (at junction, and approx 50m north on Pedders Lane): Investigation, design and corrective measures to redirect water off the highway	£15,000
19/20 Storrs Lane, Silverdale	Lancaster Rural North	Lancaster	Investigate culvert as possible collapse	£15,000
19/20 Gincroft Lane, Edenfield	Rossendale South	Rossendale	Ground water seeping through carriageway. Install new interception drain and channels	£20,000
19/20 Clod Lane, Haslingden	Rossendale South	Rossendale	Ground water eroding edge of carriageway. Improve existing drainage system and install channels	£35,000
Forecast Outturn Capital Expenditure:				£1,000,000